



## ABBREVIATIONS

●	AT
AFF	ABOVE FINISHED FLOOR
ALUM	ALUMINUM
APPROX	APPROXIMATE
ARCH	ARCHITECT
ASSOC.	ASSOCIATE
BD.	BOND
BLDG.	BUILDING
BLK	BLOCK
B.O.	BOTTOM OF
BOT.	BOTTOM
BTWN	BETWEEN
CAB.	CABINET
C.B.	CATCH BASIN
CEM.	CEMENT
C.G.	CORNER GUARD
CHAN.	CHANNEL
CLQ.	CESING
CL.	CENTER LINE
CLF.	CHAIN LINK FENCE
CLO.	CLOSET
CLR.	CLEAR
COL.	COLUMN
CONC.	CONCRETE
CONSUL.	CONSULTANT
CONT.	CONTINUOUS
COORD.	COORDINATE
CRFS	COMPOSITE REIN FIRE SNIF
CT.	CERAMIC TILE
DEMO.	DEMOLITION
DEPT.	DEPARTMENT
DETOS.	DETAILED
D.F.	DRAINING FOUNTAIN
DIA.	DIAMETER
DN.	DOWN
DWG.	DRAWING
EA.	EACH
ETC.	ET CETERA
E.DWG.	ELECTRICAL DRAWING
EL.	ELEVATION
ELEC.	ELECTRICAL
ELEV.	ELEVATOR

ENG.	ENGINEER
EQ.	EQUAL
EQUP.	EQUIPMENT
EMC.	ELECTRIC WATER COOLER
ENOT.	ENVELOPE
EXP. JT.	EXTENSION JOINT
FDN.	FOUNDATION
FE	FIRE EXTINGUISHER
FF.	FINISHED FLOOR
FLR.	FLOOR
FTG.	FOOTING
GA.	GALVANEED
GALV.	GALVANIZED
GEN.	GENERATOR
G.C.	GENERAL CONTRACTOR
GLASS	GLASS
GWB.	Gypsum WALL BOARD
H.C.	HANDICAPPED
HA	HOLLOW METAL
HCYKZ.	HORIZONTAL
HT.	HEIGHT
ID.	INSIDE DIMENSION
INSUL.	INSULATION
J.C.	JANITOR'S CLOSET
L.	LONG
LAM.	LAMINATED
LN.	LINEAR
LL.	LINE LOAD
LLV.	LONG LEG VERTICAL
MAINT.	MAINTENANCE
MAX.	MAXIMUM
M.DWG.	MECHANICAL DRAWING
MECH.	MECHANICAL
MER.	MECHANICAL EQUIPMENT ROOM
MEZZ.	MESSENGER
MIN.	MINIMUM
MISC.	MISCELLANEOUS
M.O.	MASONRY OF SETTING
M/R	MOISTURE RESISTANT
MTL.	METAL
NIC.	NOT IN CONTRACT
NOM.	NOMINAL
NTS.	NOT TO SCALE
O.A.W.	OVER-ALL WIDTH

OAL	OUTSIDE AIR INTAKE
O.C.	ON CENTER
O.D.	OUTSIDE DIAMETER
OFF.	OFFICE
OH.	OVERHEAD
OPER.	OPERATOR
OPNG.	OPENING
PL.	PLATE
PLAS.	PLASTIC
PROJ.	PROJECT
P.S.F.	POUNDS PER SQUARE FOOT
P.S.I.	POUNDS PER SQUARE INCH
P.T.	PRESSURE TREATED
PTD.	PAINTED
QT.	QUARTY TILE
R.	ROOM
REF.	REFLECTOR
RENF.	REINFORCED
REOD.	REQUIRED
RM.	ROOM
S.F.	SQUARE FEET
S.T.	STRUCTURAL FACE TILE
S.L.V.	SHORT LEG VERTICAL
SMB.	SHEET METAL SCREWS
SPCQ.	SPACING
SS.	STAINLESS STEEL
STD.	STANDARD
STL.	STEEL
STOR.	STORAGE
SVS.	SYSTEM
TECH.	TECHNICAL
THK.	THICK
T.O.	TOP OF
T.O.C.	TOP OF CONCRETE
T.O.S.	TOP OF STEEL
TYP.	TYPICAL
VAR.	VARIABLE
VCT.	VINYL COMPOSITION TILE
VERT.	VERTICAL
VEST.	VESTIBULE
VLF.	VERIFY IN FIELD
VT.	VINYL TILE
W.	WITH
W.W.M.	WELDED WIRE MESH

Sheet 2 of 8

THE PORT AUTHORITY  
OF NY & NJ

Peter K. Swamy  
ENGINEERING PROGRAM MANAGER - WTC  
M.A.  
CHIEF ARCHITECT

James D. Doherty  
Engineering Program Manager

13/6/01 Drawing of Record  
No. Date Revision Approved

Engineering Department  
Design Divisions

World Trade  
Center

ONE AND TWO  
WORLD TRADE CENTER  
FLOORS 7, 41, AND 75  
MER. SETBACKS  
ASBESTOS ABATEMENT  
AND REROOFING  
GENERAL  
LOCATION PLAN, GENERAL  
NOTES, SYMBOL LEGEND  
ABBREVIATIONS AND LIST  
OF DRAWINGS

This drawing is subject to conditions of contract.  
All inventors, designers, and drafters are to be held  
liable for the accuracy of the information and data  
submitted to the Port Authority.

L.H.B. L.H.B. A.G.S.  
Date 6-21-96 Scale AS SHOWN

Contract Number Drawing Number

WT-115.286 G-2

## GENERAL NOTES

- ALL WORK IS TO CONFORM TO ALL APPLICABLE REQUIREMENTS OF LOCAL, STATE AND FEDERAL GOVERNING CODES INCLUDING N.Y.C. CODES, OSHA, AMERICAN WITH DISABILITIES ACT, FIRE DEPARTMENT REGULATIONS, UTILITY CODES, PORT AUTHORITY STANDARDS AND BEST TRADE PRACTICES.
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO INSTALLATION OR ORDERING OF ANY WORK.
- CONTRACT DRAWINGS ARE NOT TO BE SCALED, USE DIMENSIONS ONLY. DISCREPANCIES OR ERRORS IN THE CONTRACT DRAWINGS, SPECIFICATIONS AND FOR DETAILS MUST BE REPORTED TO THE ENGINEER PRIOR TO THE START OF WORK.
- ALL WORK SHALL BE EXECUTED IN ACCORDANCE WITH THE BEST ACCEPTED TRADE PRACTICES AND AS PER THE MANUFACTURERS WRITTEN RECOMMENDATIONS.
- CONTRACTOR SHALL LAUNCH HIS WORK AND BE RESPONSIBLE FOR HIS CONDUCT AND SAFETY.
- ANY EXISTING WORK DAMAGED BY THE INSTALLATION OF THE WORK BY THE CONTRACTOR SHALL BE PATCHED, REPAIRED, REFINISHED AND/OR REPLACED TO THE ORIGINAL FINISH CONDITION AND TO THE SATISFACTION OF THE ENGINEER AND AT THE CONTRACTORS SOLE EXPENSE.
- ALL WORK SHALL BE INSTALLED SO THAT ALL PARTS EXPOSED ARE VISIBLY ACCESSIBLE FOR INSPECTION, OPERATION, MAINTENANCE AND REPAIR.
- DETAILS SHOWN ON THE DRAWINGS MAY NOT INDICATE EXACT ROOM NO. OR DIMENSIONS, BUT ONLY TYPICAL DIMENSIONS AND FINISHES. THE CONTRACTOR SHALL INCLUDE ALL ITEMS AND APPROVED TRADE PRACTICES AND FINISHES BY THE CONTRACT DRAWINGS AND THE SPECIFICATIONS.
- REMOVAL OF THE EXISTING ROOFING AND APPURTENANCES SHALL BE COORDINATED WITH THE INSTALLATION OF ROOFING AND ANY OTHER WORK OF THIS CONTRACT. ONLY AN AMOUNT OF ROOFING SHALL BE REMOVED IN ONE WORK DAY THAT SHALL NOT EXCEED AN AMOUNT OF ROOFING THAT SHALL BE INSTALLED IN THE SAME DAY.
- AFTER REMOVAL OF EXISTING ROOFING CONTRACTOR SHALL REPAIR DEFICIENCIES OF EXISTING STRUCTURAL ROOF DECK AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE COMPENSATED ON A NET BASIC COST BASIS. "NET COST" SHALL BE COMPUTED IN THE SAME MANNER AS IN COMPENSATION FOR EXTRA WORK, INCLUDING ANY PERCENTAGE ADDITION TO COST, AS SET FORTH IN THE CLAUSE OF THE CONTRACT PROVIDING COMPENSATION FOR EXTRA WORK. FINISHES AND/OR SUCH NET COST WORK SHALL BE SUBJECT TO ALL PROVISIONS OF THE CONTRACT RELATED TO PERFORMANCE OF SUCH WORK. COMPENSATION FOR NET COST WORK SHALL NOT BE CHARGED AGAINST THE TOTAL AMOUNT OF COMPENSATION FOR SUCH NET COST WORK SHALL NOT BE CHARGED AGAINST THE TOTAL AMOUNT OF COMPENSATION AUTHORIZED FOR EXTRA WORK.
- REPLACE ALL FLOOR DRAIN COVERS AND BASE COLLARS ROD OUT ALL EXISTING DRAIN LEADERS TO ASSURE PROPER FUNCTION.
- AREA FOR CONTRACTORS USE TO BE PROVIDED BY THE FACILITY.
- FINISH MEMBRANE SURFACE SHALL BE SAND BROADCAST INTO LIQUID MEMBRANE AND COATED WITH RESIN.

## SYMBOL LEGEND

	ELEVATION DESIGNATION
	BUILDING SECTION INDICATOR
	SECTION INDICATOR
	DETAIL MARKER
	ELEVATION MARKER
	ROOM NUMBER INDICATOR
	DOOR NUMBER INDICATOR
	WINDOW NUMBER INDICATOR
	PARTITION NUMBER INDICATOR
	REVISION NUMBER INDICATOR
	EXIT SIGN INDICATOR
	SPEAKER INDICATOR

## DRAWING LIST

- GENERAL**
- G-1 TITLE SHEET
  - G-2 LOCATION PLAN
  - G-3 GENERAL NOTES
  - G-4 SYMBOL LEGEND
  - G-5 ABBREVIATIONS AND LIST OF DRAWING
- ARCHITECTURAL**
- A-1 ONE WORLD TRADE CENTER 7th, 41st and 75th FLOOR PLANS
  - A-2 TWO WORLD TRADE CENTER 7th, 41st and 75th FLOOR PLANS
  - A-3 SECTIONS AND DETAILS
- ENVIRONMENTAL**
- EA-1 TYPICAL FLOOR PLAN
  - EA-2 TYP SECTION AND ROOF DETAILS
  - EA-3 STANDARD DETAILS SHEET 1